



Rig #1

Specification Sheet

Type of Rig: Free Standing Mobile Single

Make & Model: Global 42 x 10

Capacity: 2500m

Engine: Detroit 60 Series 425 HP

Transmission: Allison 4700 OFS

Crew: 5 Man

Built: October 2012



Mast

- Height: 22.25 m
- Capacity: 62,200 daN
- Single Tubing
- Double Rod

Equipment Trucks

- 5 ton International
- BOP Pressure Testing Stump
- Built September 2012

Handling Equipment

- Tubing Tongs, Slips and Elevators for 60.3 mm - 88.9 mm Tubing
- Rod Hook, Wrenches and Elevators: 16 mm - 25.4 mm Rods
- Rod Tongs: 16 mm - 25.4 mm Rods
- Swab Equipment: 60.3 mm - 177.8 mm
- Guiberson Type "HD" Saver Head
- Low Lying Slips
- Drill-Out Head

Safety Equipment

- Tubing Safety Valve: 73mm and 89mm
- 2 SCBA and 2 spare bottles
- 4-30 lb. Fire Extinguisher
- Mast Climbing Device
- Rig Rescue Kit
- First Aid Kit

Drawworks

- 42 x 10 x 1" Main Drum
- Kobelt 40" Auxiliary Disk Brake
- 3000 m of 9/16" Sandline

Dog House

- 2.8 m x 12 m Pintle Hitch
- Isuzu 20 kW Light Plant
- Built September 2012

Pump & Tank - Mobile

- SJ Petro 5X5
- 35,000 kPa Pump and Manifold
- 35,000 kPa Line Pipe
- Tank Size: 30 m³ with Degasser
- Mud Hopper Mixing System
- Jets
- Built September 2012

B.O.P. System

- Class II
- Unity Rig 179.4 mm
- 100 Liter Accumulator
- 35,000 kPa Double Gate Bop's